

#### GOVT. OF WEST BENGAL OFFICE OF THE DISTRICT MAGISTRATE BACKWARD CLASSES WELFARE & TRIBAL DEVELOPMENT DAPARTMENT 2 ND FLOOR, ADMINISTRATIVE BUILDING, DAKSHIN DINAJPUR, BALURGHAT

Ph. No./ FAX: 03522-255624

email: pobcwdd@gmail.com

Memo No :424/BCW&TDD(DD)

Dated: 29.03.2018

#### NOTICE INVITING QUOTATION 9(Nine) of 2017-18

Sealed quotation are invited from bonafied contractor for the following items in the office of the undersigned having fulfillment of following terms and conditions. Intending contractors, put their quotation in their pad in sealed envelope within 04.04.2018 up to 2.00 P.M. at the chamber of P.O. cum D.W.O., B.C.W.D. & T.D.D., Dakshin Dinajpur and the tenders shall be opened at the same day at 3.30 P.M.

#### **TERMS & CONDITIONS**

- Only the reputed contractors can participate in the quotation process and he/she will have to submitted the self attested copy the Trade License, Professional Tax Assessment (Clearance Certificate up to date) and GSTIN No. in his/her own name or Farm (Clearance Certificate and audit report up to date), PAN card no, (3 years IT clearance 2.
- The price as quoted must be inclusive of all taxes
- Incomplete quotation will be rejected summarily.
- All works will have to be done according to following specification as approved by authority and as per direction of the Project Officer cum District Welfare Officer, Backward Classes Welfare & Tribal Development Department, Dakshin
- The Quatation received after the due date and time and any change in NIQ after opening of rate will be out rightly rejected. The undersigned will not be responsible for the loss of Tender Form or for the delay in the posted transit.
- Works must be completed within 15 days after receiving of work order.
- Payment will be made from the end of P.O. cum D.W.O., Backward Classes Welfare & Tribal Development Department, Dakshin Dinajpur, Balurghat directly and necessary deduction (IT, cess) is applicable as per Govt. norms 8.
- The authority reserves the right of accepting and rejecting any of the quotation without assigning any reason thereof.
- The contractor have to quote rate in the format given below on his original letter head paper.

### DESCRIPTION OF WORKS

Name of works	Estimated Amount (INID)	
Repair & Renovation of Physics Laborate	Estimated Amount (INR)	Quoted rate of Worl
under Ballstillari Block of Dakshin Dinainur Dietrict	99,959.00	
Repair & Renovation of Chamistry, Laboratory		
Buildapur under Bansninari Block of Dakehin Dinginus Division	07,416.00	
Repair & Renovation of Biology Leb		
under Banshihari Block of Dakshin Dinaipur District	67,416.00	
	Repair & Renovation of Chemistry Laboratory at EMRS, Buniadpur under Banshihari Block of Dakshin Dinajawa Discourse	Repair & Renovation of Physics Laboratory at EMRS, Buniadpur under Banshihari Block of Dakshin Dinajpur District  Repair & Renovation of Chemistry Laboratory at EMRS, Buniadpur under Banshihari Block of Dakshin Dinajpur District  Repair & Renovation of Biology Laboratory at EMBS, Buniadpur Under Banshihari Block of Dakshin Dinajpur District  Repair & Renovation of Biology Laboratory at EMBS, Buniadpur District

Project Officer cum District Welfare Officer Backward Classes Welfare & Tribal Development Department, Dakshin Dinajpur, Balurghat

Dated: 29.03.2018

Memo No: 424/1(2)/BCW&TDD(DD)

Copy forwarded for kind information and wide publicity to:

The DIO, NIC, Dakshin Dinajpur with a request to upload the NIQ with 3 copy of Estimate in the District website

Project Officer cum District Welfare Officer Backward Classes Welfare & Tribal Development Department, Dakshin Dinajpur, Balurghat

1 to 1

## Repair & Renovation of Biology Laboratory at EMRS, Buniadpur under Banshihari Block of Dakshin Dinajpur District

SI no					
1	P/64 It No/35 Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile & finishing the joints with white cement mixed with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary or by synthetic adhesive & grout materials etc  (A) Floor With Sand Cement Mortar (1:4) 20 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sq.m  (b) Area of each tile above 0.09 Sq.m	Quan	tity	Rate	Amou
(I V th 2. (a ii)	(i) Coloured decorative Class Room  B) Wall With Sand Cement Mortar (1:3) 15 mm thick & 2 mm hick cement slurry at back side of tiles using cement @ .91 Kg/Sq.m & joint filling using white cement slurry @ .20kg/Sq.m. b) Area of each tile upto 0.09 Sq.m Other than Coloured decorative including white ass Room	5.40 x 4.95	26.73 sqm 26.73 sqm	904.00 / sqm	24163.9
P/:	194 It No/04	2 x 5.40 x 2.30 2 x 4.95 x 2.30	24.84 sqm 22.77 sqm 47.61 sqm	703.00 / sqm	22450.00
Dr cle (i) I (a)	y Distemparing to interior walls or ceiling including raning, washing, smoothening surface Internal surface (All floors) One coat of colour wash Other than yellow, pink	2 x 5.40 x 1.00 2 x 4.95 x 1.00	26.73 sqm 10.80 sqm 9.90 sqm	7 3411	33469.83
	. 77		47.43 sqm	33.00 / sqm	1565.19

59198.94 Add GST @ 9.5 % 5623.90

Cost of Civil works excluding Labour Welfare Cess 64822.84 Add Labour Welfare Cess

648.23 Add 3% Contingency

1944.69 Grand Total 67415.75

67416.00

Rupees Sixty Five Thousand Four Hunderd and Sixteen only

26.03.18 Junior Engineer

BCW & TDD, D. Dinajpur

20/03/2018 Assistant Engineer ITDA, Buniadpur, DD

## Repair & Renovation of Physics Laboratory at EMRS, Buniadpur under Banshihari Block of Dakshin Dinajpur District

Sino	Description of Items				
	P/64 It No/35  Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile & finishing the joints with white cement mixed with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary or by synthetic adhesive & grout materials etc  (A) Floor  With Sand Cement Mortar (1:4) 20 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sq.m  (b) Area of each tile above 0.09 Sq.m  (i) Coloured decorative  Class Room  (B) Wall  With Sand Cement Mortar (1:3) 15 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 1.50 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 1.50 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 1.50 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 1.50 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 1.50 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 1.50 mm thick & 2 mm thi	Quan 9.00 x 4.95	44.55 sqm 44.55 sqm	904.00 / sqm	Amoun
(a (ii) C	91 Kg/Sq.m & joint filling using white cement slurry @ 20kg/Sq.m. a) Area of each tile upto 0.09 Sq.m ) Other than Coloured decorative including white lass Room	2 x 9.00 x 2.30 2 x 4.95 x 2.30	41.40 sqm 22.77 sqm 64.17 sqm	703.00 / sqm	45111.51
Di cle (i) (a)	ry Distemparing to interior walls or ceiling including eaning, washing, smoothening surface Internal surface (All floors) One coat of colour wash Other than yellow, pink	2 x 9.00 x 1.00 2 x 4.95 x 1.00	44.55 sqm 18.00 sqm 9.90 sqm	2500 / 34111	45111.51
	, 7		72.45 sgm	33.00 / sqm	2390.85

87775.56 Add GST @ 9.5 % 8338.68 Cost of Civil works excluding Labour Welfare Cess 96114.24 Add Labour Welfare Cess 961.14 Add 3% Contingency 2883.43 **Grand Total** 99958.81 99959.00

Rupees Ninety Nine Thousand Nine Hunderd and Fifty Nine only 26/03/2018

Junior Engineer BCW & TDD, D. Dinajpur

Assistant Engineer ITDA, Buniadpur,DD

# Repair & Renovation of Chemistry Laboratory at EMRS, Buniadpur under Banshihari Block of Dakshin Dinajpur District

	SI no Description of Items	1			
	1.704/11/0/35	, OI	antity		
	Supplying, fitting & fixing 1st quality Ceramic tiles in wand floors to match with the existing work & 4 nos. of stones (10mm) fixed with araldite at the back of each & finishing the joints with white cement mixed with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary by synthetic adhesive & grout materials etc  (A) Floor  With Sand Cement Mortar (1:4) 20 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sa.m  (b) Area of each tile above 0.09 Sq.m  (i) Coloured decorative	valls key tile or		Rate	Amou
	Class Room  (B) Wall  With Sand Cement Mortar (1:3) 15 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sq.m.  (a) Area of each tile upto 0.09 Sq.m  ii) Other than Coloured decorative including white Class Room	5.40 x 4.95	26.73 sqm 26.73 sqm	904.00 / sqm	24163.92
2	P/194 It No/04 Dry Distemparing to interior walls or ceiling including cleaning, washing, smoothening.	2 x 5.40 x 2.30 2 x 4.95 x 2.30	24.84 sqm 22.77 sqm 47.61 sqm	703.00 / sqm	
- 1	cleaning, washing, smoothening surface (i) Internal surface (All floors) (a) One coat of colour wash (i) Other than yellow, pink	2 x 5.40 x 1.00 2 x 4.95 x 1.00	26.73 sqm 10.80 sqm 9.90 sqm 47.43 sqm	33.00 / sqm	33469.83

59198.94 Add GST @ 9.5 % 5623.90

Cost of Civil works excluding Labour Welfare Cess 64822.84 Add Labour Welfare Cess

648.23 Add 3% Contingency 1944.69

Grand Total 67415.75

Rupees Sixty Five Thousand Four Hunderd and Sixteen only

Junior Engineer BCW & TDD, D. Dinajpur

Assistant Engineer ITDA, Buniadpur,DD